

Case Study

Tenax HM Geogrids Ekotex® Non Woven Geotextile UHCW Staff Car Park



Location:

Clifford Bridge Road
Walsgrave
Coventry



Client:

University Hospitals Coventry
& Warwickshire / Prime

Contractor:

Montel Civil Engineering

Subcontractor

Barton Plant

Consultant / Engineer:

One Creative Environments

Merchant:

 **Keyline**
CIVILS SPECIALIST

University Hospital Coventry and Warwickshire was opened in 2006 on the site of the original Walsgrave Hospital. In an attempt to free up parking for visitors an application was made to construct a 1600 space staff car park on available land to the rear of the existing site boundary. Montel Civil Engineering were awarded the contract to construct the car park and One Creative Environments were appointed as designers. Montel approached Geosynthetics to determine suitability of a geogrid solution to reduce aggregate thickness and excavation / muckaway costs. The approximate area was 36,000m²

Due to the varied soil test results on the site, it was proposed that the overall area was zoned to optimise the savings in aggregate. With CBR's ranging from 1% to 10% it was agreed that Geosynthetics would run calculations for 10 zones using both the Tenax Reinforced Soil Raft and AASHTO ESAL design methods. The calculations were able to determine a reduction in aggregate thickness of typically 25-30% when compared to a traditional unreinforced solution. The geogrids were installed in a single layer directly upon a layer of Ekotex® non woven geotextile. This solution was used in both traditional sub base and permeable sub base areas to incorporate the projects drainage design.

By employing a practical approach Geosynthetics working with One Creative were able to reduce the overall depth and stone and associated excavation and muckaway costs. This collaborative approach was able to generate the results that the main contractor had envisaged and had a positive influence on the earth works strategy.



The approach taken by Geosynthetics allowed us to optimise the pavement construction and minimise imported granular material, removal and export of surplus soils. Whilst generating cost savings this approach also has a positive influence on time scales and project programme.

Kelvin Lewis - Project Manager

Geosynthetics Limited
Fleming Road
Harrowbrook Industrial Estate
Hinckley
LE10 3DU

T: 01455 617 139
sales@geosyn.co.uk
www.geosyn.co.uk



2 in 1
Landscaping Fabric



Gas Membrane
Radon, CO2, Methane,
Hydrocarbon Control



RoofCell
Sub Surface Drainage
And Water Storage



Alert®
Contamination Indicator



Geoglas®
Asphalt Reinforcement



Stratagrid
Soil Reinforcement Geogrid



AquaBlock®
Water Containment Liners



Geomembrane
Impermeable Membrane




Strataweb
Slope Stabilisation



Bentotex® GCL
Geosynthetic Clay Liner



Golpla
Grass & Gravel Paving System



T-Block
Modular Retaining System



Cellweb® TRP
Tree Root Protection



Golpla Pregrown
Ready To Lay Paving System




Telegrid
Woven Polyester Geogrid



DuoDrain®
Composite Drainage Product



Interlock
Extruded HDPE Geogrids



Televev
High Strength
Woven Geotextile



Erosion Control
Comprehensive Range



Knotblock®
Japanese Knotweed Barrier



Tenax
Soil Reinforcement Solutions



Ekotex®
Non Woven Geotextile



Landlok
Turf Reinforcement Mat



Total Traffic Exopave
Heavy Duty Paver




Fiberforce®
Equestrian Geotextile



Nicospan
Erosion Control



Trinter
Erosion Control Mat




Fibertex
Non Woven Geotextile



Rhyno®
Woven Geotextile



Turfmesh
Grass Reinforcement




Flexitex
Textile Shuttering



RockBox
Gabion Mattresses



RootBlock
Root Barrier




INVESTORS
IN PEOPLE

Bronze